

### ADD ALTERNATE BID

The qualities listed below are based on the Southern Motor Coach (DP2010-0062) construction plans that were approved by Sumter County on February 23, 2011. The improvements to CR 673 shown on the construction plans are associated with the pavement widening to accommodate a turn lane, taper and driveway.

Paving	QTY.	UNIT	UNIT price	Extended Amount
Pavement Widening - 2" open-graded mix	1,600	SY	8.00	12,800.00
Pavement Widening - 13.5" Limerock Base	1,600	SY	11.00	17,600.00
1.5" SP 12.5, Traffic B	1600	SY	8.00	12,800.00
Sod Disturbed Areas	4,000	SY	1.75	7,000.00
Earthwork Sta 40+00 - 51+00*	1	LS	21,000.00	21,000.00
Thermoplastic Striping*	1	LS	1,500.00	1,500.00
Add Alternate Total				72,700.00

\* Turn Lane Construction Only

Seventy Two Thousand Seven Hundred Dollars & No Cents

("Add Alternate" total in words)